

Projects

Blosenski Landfill Superfund Site

West Caln Township



Project Information

Client: de maximis, inc.

Conti Role: Prime Contractor

Contract Type: Fixed Price

Type of Work: Landfill Closure

Contract Value: \$2,500,000

Contaminants: Solvent, chlorine

Period: 5/1995 – 11/1996

This 13.6-acre landfill superfund site operated as a sanitary landfill but also accepted industrial waste, including large amounts of drummed chemical waste.

Scope of Work

- Implemented the closure of the site, which consisted of the installation of a multi-media cap over approximately 7.5 acres.
- Cap consisted of a geomembrane liner and geotextile drainage layer, followed by soil cover.
- Regraded, which involved the excavation and relocation of refuse from specifically identified areas.
- During the course of the regading activity, discovered, removed, overpacked, and staged for sampling, analysis and disposal over 500 drums.
- Mobilized personnel and equipment capable of conducting drum handling operations in Level B personal protective equipment.
- Provided all of the required services for this unanticipated activity including full health and safety monitoring and initial drum screening and documentation.